



PURCHASE ORDER

Plot no 81, Desk no: 01, Poriayar Nagar,
4th Street, Thiruppalai, Madurai - 625014
Email: accounts@bkgreenenergy.com Ph:7539944358
GSTIN: 33DYJPK9079P1ZF

SUPPLIER NAME & ADDRESS:

K.S.GROUPS

17/A, New Street, Sorathur & Post,
Panruti Taluk, Cuddalore-Dist, Tamil Nadu.
GSTIN : 33AATFK1263E1ZF

DISPATCHED TO:

Torrent Urja 22 PVT LTD

Phoenix Mill solar PV Plant,
Ullendrupet , Tamil Nadu.

Purchase Order#

BKGE/001/2526

DATE

13/10/2025

Reference No

Sl No	HSN#	Description	Unit	Quantity	Price	Tax	Amount
-------	------	-------------	------	----------	-------	-----	--------

1	-	Marking, Auguring, Piling, Alignment and Piping, Coping, Casting 300 mm Dia 1.5 Depth	NOS	3500	1250	18%	₹5,162,500.00
---	---	--	-----	------	------	-----	---------------

₹4,375,000.00 ₹787,500.00 ₹5,162,500.00

Round Off ₹0.00

TOTAL

TOTAL ₹5,162,500.00

This Purchase Order was generated with the help of Athenas.

Scope of Work:

1. The following activities are included within the vendor's scope:
2. Survey and Marking – Conduct site survey and marking of pile locations as per approved drawings.
3. Alignment – Ensure proper alignment and positioning prior to auguring.
4. Auguring – Carry out auguring work to the specified depth and diameter as per design requirements.
5. Pile Concreting (M25 Grade) – Execute pile concreting using M25 grade concrete, ensuring quality and uniformity.
6. Pile Capping (150 mm Thickness) – Provide and complete 150 mm thick capping for all piles.
7. Application of Curing Compound – Apply curing compound immediately after concreting to ensure proper curing.
8. Templates and Capping Pipes – Supply, fix, and remove templates and capping pipes as required.

Additional Requirements:

1. Cube Tests: Concrete cube tests must be conducted on time and results submitted for approval.
2. Design Mix Report: The approved design mix report shall be submitted prior to commencement of concreting work.

Payment Terms

Payment Condition:

1. Payment shall be released upon completion of 1,000 piling works in accordance with approved specifications and quality standards.
2. Upon completion of the 1,000 piles and submission of the corresponding invoice, payment will be released within 15 days from the date of invoice receipt.

Rate Condition

1. As per the quotation, the piling rate is fixed and shall remain unchanged irrespective of any natural hazards, site conditions, or minor unforeseen defects encountered during execution. (This means that any challenges arising from normal site variations, soil conditions, or natural obstacles will not affect the agreed rate.)

Note: The only exception is if DTH (Down-The-Hole) auguring becomes necessary due to exceptionally hard strata or conditions not covered in the original scope; in such a case, the rate may be revised upon mutual agreement.

Vendor Acceptance

Please review this document, accept the terms, and return it with your signature and company seal.